

**NEW YORK STATE THRUWAY AUTHORITY  
WILLIAMSVILLE TOLL BARRIER IMPROVEMENT PROJECT  
NYSTA CONTRACT NO. D212607**

**DESIGN REPORT/DRAFT ENVIRONMENTAL IMPACT STATEMENT**

**TABLE OF CONTENTS**

	<u>Page</u>
<b>VOLUME I: MAIN DOCUMENT (Revised May 2006)</b>	
<b>COVER PAGE</b>	
<b>TITLE SHEET</b>	
<b>EXECUTIVE SUMMARY</b>	
<b>TABLE OF CONTENTS</b>	i
<b>CHAPTER I - INTRODUCTION</b>	I-1
<b>CHAPTER II - PROJECT IDENTIFICATION, EVOLUTION, CONDITIONS AND NEEDS, AND OBJECTIVES</b>	II-1
II.A. Project Identification	II-1
II.A.1. Project Type	II-1
II.A.2. Project Location/Description	II-1
II.B. Project Evolution	II-2
II.C. Conditions and Needs	II-9
II.C.1. Transportation Conditions, and Engineering Considerations	II-9
II.C.1.a. Functional Classification and National Highway System (NHS)	II-9
II.C.1.b. Ownership and Maintenance Jurisdiction	II-9
II.C.1.c. Culture, Terrain and Climatic Conditions	II-9
II.C.1.d. Control of Access	II-13
II.C.1.e. Existing Williamsville Toll Barrier	II-13
II.C.1.f. Existing Highway Section along Project Corridor	II-23
II.C.1.g. Interchange 49 and Toll Plaza	II-27
II.C.1.h. Abutting Highway Segments and Future Plans for Abutting Highway Segments	II-29
II.C.1.i. Existing and Future (No-Build) Travel Speeds	II-30
II.C.1.i.(1) Existing Speed Limits	II-30
II.C.1.i.(2) Operating Speeds	II-31
II.C.1.j. Traffic Volumes	II-31
II.C.1.k. Level of Service and Delay	II-32
II.C.1.k.(1) Existing Level of Service and Delay-Highway Segments	II-33
II.C.1.k.(2) Future No-Build Level of Service-Highway Segments	II-33
II.C.1.k.(3) Existing Delay Estimate at Toll Barrier & Plazas	II-34
II.C.1.k.(4) Future No-Build Delay Estimate at Toll Barrier and Plazas	II-35

**NOTE: Each Figure and Table NOT embedded in the text is considered two pages (front & back) for page numbering purposes.**

II.C.1.i.	Nonstandard Features and Other Non-Conforming Features of the Existing Toll Barrier	II-35
II.C.1.m.	Accident Analysis	II-37
II.C.1.n.	Pavement and Shoulder Conditions	II-39
II.C.1.o.	Guide Rail, Median Barrier, Impact Attenuators	II-41
II.C.1.p.	Traffic Control Devices	II-41
II.C.1.q.	Structures	II-42
II.C.1.r.	Hydraulics of Bridges and Culverts	II-45
II.C.1.s.	Drainage Systems	II-45
II.C.1.t.	Soil and Foundation Conditions	II-45
II.C.1.u.	Utilities	II-46
II.C.1.v.	Railroads	II-48
II.C.1.w.	Visual Environment	II-48
II.C.1.x.	Provisions for Pedestrians and Bicyclists	II-49
II.C.1.y.	Planned Development for the Area	II-49
II.C.1.z.	System Elements and Conditions	II-50
II.C.1.aa.	Environmental Integration	II-51
II.C.2.	Needs	II-51
II.C.2.a.	Project Level Needs	II-51
II.C.2.b.	Transportation Plans	II-53
II.D.	Project Objectives	II-53
<b>CHAPTER III - ALTERNATIVES</b>		<b>III-1</b>
III.A.	Design Criteria	III-1
III.A.1.	Standards	III-1
III.A.1.a.	Toll Barrier Structures	III-1
III.A.1.b.	Highway Elements	III-1
III.A.2.	Critical Design Elements	III-1
III.A.2.a.	Toll Barrier	III-1
III.A.2.b.	Highway Elements	III-3
III.B.	Alternatives Considered	III-4
III.B.1.	No Build Alternative	III-4
III.B.2.	Build Alternative	III-9
III.B.2.a.	Toll Barrier Elements	III-9
III.B.2.b.	Approach/Departure Highway Elements	III-13
III.B.2.c.	Alternative Toll Barrier Configurations	III-14
III.B.2.d.	Improvement Alternative	III-18
III.B.2.e.	Relocation Alternative	III-37
III.B.2.e.(1)	Study Corridor	III-41
III.B.2.e.(2)	Identification of Potential Relocation Sites	III-41
III.B.2.e.(3)	Comparative Evaluation of Potential Relocation Sites	III-42
III.B.2.e.(3)(a)	Siting Criteria	III-42
III.B.2.e.(3)(b)	Engineering Criteria	III-42
III.B.2.e.(3)(c)	Environmental Criteria	III-45
III.B.2.e.(3)(d)	Relative Site Suitability Scoring & Ranking	III-46
III.B.2.e.(3)(e)	Identification of Most Suitable Relocation Sites	III-46
III.B.2.e.(4)	Bridge Clearance Implications	III-59
III.B.2.e.(5)	Comparison of Hybrid Alternative Scenario ES-2A	III-59
III.B.2.e.(6)	Conclusion	III-62
III.B.3.	Transportation System Management (TSM) Alternative	III-62

	III.B.3.a. Context of Operations	III-62
	III.B.3.b. TSM Alternatives Considered	III-64
	III.B.4. Mass Transit Alternative	III-65
III.C.	Feasible Alternatives	III-66
	III.C.1. Description of Feasible Alternative(s)	III-66
	III.C.1.a. No Build Alternative	III-66
	III.C.1.b. Improvement Alternative	III-67
	III.C.1.c. Relocation Alternative	III-67
	III.C.1.c.(1) Relocation Sites	III-67
	III.C.1.c.(2) Existing Williamsville Toll Barrier and Interchange 49 Toll Plaza	III-69
	III.C.2. Engineering Considerations of Feasible Alternative(s)	III-69
	III.C.2.a. Special Geometric Features	III-69
	III.C.2.b. Traffic Forecasts, Level of Service and Safety Considerations	III-70
	III.C.2.b.(1) Estimated Time of Completion and Design Year Traffic Volumes	III-70
	III.C.2.b.(2) Delay Analyses and Level of Service	III-79
	III.C.2.b.(3) Safety Considerations	III-84
	III.C.2.c. Pavement	III-84
	III.C.2.d. Facilities	III-85
	III.C.2.e. Bridges	III-90
	III.C.2.f. Hydraulics	III-92
	III.C.2.g. Drainage	III-92
	III.C.2.h. Maintenance Responsibility	III-92
	III.C.2.i. Maintenance and Protection of Traffic	III-93
	III.C.2.j. Soil Foundation	III-94
	III.C.2.k. Utilities	III-95
	III.C.2.l. Railroads	III-99
	III.C.2.m. Right-of-Way	III-99
	III.C.2.n. Landscaping Development	III-102
	III.C.2.o. Provisions for Pedestrians, Including Persons with Disabilities	III-103
	III.C.2.p. Provisions for Bicycling	III-103
	III.C.2.q. Lighting	III-103
	III.C.2.r. Implementation Options	III-105
	III.C.2.r.(1) Full Build-Out	III-105
	III.C.2.r.(2) East/West Phased Implementation	III-106
	III.C.2.r.(3) Staged Construction of Manual Toll Collection Lanes	III-106
III.D.	Project Costs and Schedule	III-108
	III.D.1 Costs	III-108
	III.D.1.a. Relocation Alternative	III-108
	III.D.2. Schedule	III-109
	III.D.2.a. Relocation Alternative	III-109
<b>CHAPTER IV - SOCIAL, ECONOMIC, AND ENVIRONMENTAL CONSIDERATIONS</b>		<b>IV-1</b>
IV.A	Introduction	IV-1
	IV.A.1 Requirements	IV-1
	IV.A.2 Impact Assessment	IV-1
	IV.A.3 Project Study Area	IV-1
	IV.A.4 List of Permits	IV-2
	IV.A.4.a Storm Water	IV-2
	IV.A.4.b Water Quality	IV-2
	IV.A.4.c Farmland Protection	IV-2

IV.A.4.d	Wetlands	IV-2
IV.A.5.	Social Environment	IV-3
IV.A.5.a.	Existing Communities	IV-3
IV.A.5.b.	Population	IV-3
IV.A.5.c.	Ethnic/Age Distribution	IV-3
IV.A.5.d.	Housing	IV-4
IV.A.5.e.	Community Facilities	IV-4
IV.A.6.	Economic Conditions	IV-5
IV.A.6.a.	Regional Employment	IV-5
IV.A.6.b.	Corridor Employment	IV-9
IV.A.6.c.	Corridor Development/Highway Related Businesses	IV-10
IV.A.6.d.	Established Business Districts	IV-10
IV.A.6.e.	Travel and Access Characteristics	IV-15
IV.A.7	Environmental Conditions	IV-15
IV.A.7.a	General Description	IV-15
IV.A.7.b	Key Environmental Areas	IV-16
IV.B.	Social, Economic, and Environmental Consequences	IV-19
IV.B.1.	Social Consequences	IV-19
IV.B.1.a.	Community Character	IV-19
IV.B.1.a.(1).	No-Build Alternative	IV-19
IV.B.1.a.(2).	Relocation Alternative	IV-19
IV.B.1.b.	Changes in Travel Patterns or Accessibility	IV-22
IV.B.1.b.(1).	No-Build Alternative	IV-22
IV.B.1.b.(2).	Relocation Alternative	IV-22
IV.B.1.c.	Impacts on School Districts, Recreation Areas, Churches, or Businesses	IV-24
IV.B.1.c.(1).	School Districts	IV-24
IV.B.1.c.(2).	Recreation Areas	IV-25
IV.B.1.c.(3).	Churches and Businesses	IV-25
IV.B.1.d.	Impacts on Police, Fire Protection, and Ambulance	IV-26
IV.B.1.d.(1).	Police Access	IV-26
IV.B.1.d.(2).	Fire and Ambulance Protection	IV-27
IV.B.1.d.(2)(a)	Methodology	IV-27
IV.B.1.d.(2)(b)	Existing Conditions	IV-27
IV.B.1.d.(2)(c)	Impacts	IV-28
IV.B.1.d.(2)(d)	Mitigation	IV-30
IV.B.1.d.(3)	Hospital Services	IV-30
IV.B.1.e.	Impacts on Highway Safety, Traffic Safety, and Overall Public Safety	IV-30
IV.B.1.f.	General Social Groups Benefited or Harmed	IV-31
IV.B.1.g.	Environmental Justice	IV-31
IV.B.1.g.(1).	Executed Order 12898	IV-31
IV.B.2.	Economic Consequences	IV-32
IV.B.2.a.	Impacts on Regional and Local Economies	IV-32
IV.B.2.b.	Impacts on State/Local Taxes	IV-33
IV.B.2.c.	Impacts on Travel Time Costs	IV-34
IV.B.2.d.	Local Road Costs	IV-34
IV.B.2.e.	Impacts on Highway Related Businesses	IV-35
IV.B.2.f.	Impacts on Established Business Districts	IV-35
IV.B.2.g.	Relocation Impacts	IV-36
IV.B.2.h.	Operating Cost Impacts	IV-36
IV.B.3.	Environmental Consequences	IV-37
IV.B.3.a.	Noise	IV-37
IV.B.3.a.(1).	Noise Analysis Methodology	IV-38
IV.B.3.a.(2).	Existing Conditions	IV-39
IV.B.3.a.(3).	Future Conditions	IV-40

	IV.B.3.a.(4). Abatement Measures	IV-53
	IV.B.3.a.(5). Construction Impacts	IV-55
IV.B.3.b.	Air Quality	IV-56
	IV.B.3.b.(1). Introduction	IV-56
	IV.B.3.b.(2). Background	IV-57
	IV.B.3.b.(3) Air Quality Impact Analysis	IV-58
	IV.B.3.b.(3)(a)Micro-Scale Analysis Methodology	IV-59
	IV.B.3.b.(3)(b)Micro-Scale Analysis Results	IV-60
	IV.B.3.b.(3)(c)Regional Air Quality Impacts	IV-74
	IV.B.3.b.(3)(d)Construction Emissions Impacts	IV-76
	IV.B.3.b.(4). Mitigation	IV-76
	IV.B.3.b.(5). Evaluation of Staged Construction	IV-77
IV.B.3.c.	General Ecology and Endangered Species	IV-77
	IV.B.3.c.(1). General Ecology Methodology	IV-78
	IV.B.3.c.(2). Existing Environment	IV-79
	IV.B.3.c.(3). Ecology of Alternates	IV-81
	IV.B.3.c.(3)(a)Relocation Alternative Milepost 410	IV-81
	IV.B.3.c.(3)(b)Relocation Alternative Milepost 408-409	IV-81
	IV.B.3.c.(3)(c)Relocation Alternative Milepost 404-405	IV-81
	IV.B.3.c.(4). Impacts	IV-82
	IV.B.3.c.(4)(a)Ecological Impacts	IV-82
	IV.B.3.c.(4)(b)Wildlife Impacts	IV-83
	IV.B.3.c.(4)(c)Aquatic Resources	IV-84
	IV.B.3.c.(4)(d)Threatened and Endangered Species	IV-84
	IV.B.3.c.(5) Invasive Species	IV-84
	IV.B.3.c.(6) Mitigation	IV-84
IV.B.3.d.	Wetlands	IV-85
	IV.B.3.d.(1). Methodology	IV-86
	IV.B.3.d.(2). Existing Wetlands	IV-86
	IV.B.3.d.(3). State Regulated Wetlands	IV-87
	IV.B.3.d.(4). Smaller Wetlands under Federal Jurisdiction	IV-87
	IV.B.3.d.(5). Wetland Function Analysis	IV-101
	IV.B.3.d.(6). Wetland Impacts	IV-102
	IV.B.3.d.(7). Executive Order 11990	IV-105
	IV.B.3.d.(7)(a)Avoidance	IV-106
	IV.B.3.d.(7)(b)Wetland Impact Minimization	IV-108
	IV.B.3.d.(8). Mitigation	IV-110
IV.B.3.e.	Navigable Waters	IV-111
IV.B.3.f.	Coastal Zone Management	IV-111
IV.B.3.g.	Wild, Scenic, and Recreational Rivers	IV-111
IV.B.3.h.	Critical Environment Areas (CEA's)	IV-111
IV.B.3.i.	Surface Water and Ground Water Quality	IV-111
	IV.B.3.i.(1). Methodology	IV-112
	IV.B.3.i.(1)(a)Regulatory Review and Permit Requirements	IV-121
	IV.B.3.i.(2). Existing Conditions	IV-121
	IV.B.3.i.(2)(a)Geology	IV-121
	IV.B.3.i.(2)(b)Hydrology	IV-122
	IV.B.3.i.(2)(b)(i) Surface Water	IV-122
	IV.B.3.i.(2)(b)(ii) Groundwater	IV-123
	IV.B.3.i.(3). Impacts	IV-126
	IV.B.3.i.(3)(a)Groundwater Quantity	IV-126
	IV.B.3.i.(3)(b)Surface Water and Groundwater	IV-127

	Quality	
	IV.B.3.i.(3)(b)(i) Chloride	IV-127
	IV.B.3.i.(3)(b)(ii) Heavy Metals	IV-128
	IV.B.3.i.(3)(b)(iii) Potential Spills	IV-128
	IV.B.3.i.(3)(b)(iv) Stormwater Erosion, and Sedimentation	IV-129
	IV.B.3.i.(4) Mitigation	IV-129
	IV.B.3.i.(4)(a) Surface Water Quality	IV-129
	IV.B.3.i.(4)(b) Groundwater	IV-129
	IV.B.3.i.(4)(c) Spills	IV-130
	IV.B.3.i.(4)(d) Erosion and Sedimentation	IV-131
	IV.B.3.i.(4)(e) Stormwater Runoff Impacts	IV-131
IV.B.3.j.	This Section is not used.	IV-131
IV.B.3.k.	Floodplain Management	IV-131
	IV.B.3.k.(1) Methodology	IV-131
	IV.B.3.k.(2) Existing Conditions	IV-131
	IV.B.3.k.(3) Impacts	IV-132
	IV.B.3.k.(4) Mitigation	IV-135
IV.B.3.l.	Historic and Cultural Resources	IV-135
	IV.B.3.l.(1) Methodology	IV-136
	IV.B.3.l.(2) Existing Conditions	IV-136
	IV.B.3.l.(2)(a) Prehistoric and Historic Background	IV-136
	IV.B.3.l.(2)(b) Documented Cultural Resources	IV-137
	IV.B.3.l.(2)(c) Field Conditions	IV-138
	IV.B.3.l.(3) Impacts and Assessment Results	IV-140
	IV.B.3.l.(4) Mitigation Measures and Recommendations for Additional Investigation	IV-141
IV.B.3.m.	Section 4(f) and Section 6(f) Lands	IV-141
IV.B.3.n.	Hazardous Waste and Contaminated Materials	IV-141
	IV.B.3.n.(1) Introduction	IV-141
	IV.B.3.n.(2) Methods	IV-142
	IV.B.3.n.(3) Results	IV-142
	IV.B.3.n.(3)(a) Recognized Environmental Conditions	IV-142
	IV.B.3.n.(3)(b) Other Potential Conditions	IV-143
	IV.B.3.n.(4) Mitigation	IV-143
IV.B.3.o.	Asbestos	IV-143
	IV.B.3.o.(1) Methodology	IV-144
	IV.B.3.o.(2) Existing Conditions and Results of Inspection Survey	IV-144
	IV.B.3.o.(3) Impacts	IV-145
	IV.B.3.o.(4) Mitigation	IV-146
IV.B.3.p.	Farmlands	IV-146
	IV.B.3.p.(1) Methodology	IV-147
	IV.B.3.p.(2) Existing Conditions	IV-147
	IV.B.3.p.(3) Impacts and Assessment Results	IV-148
	IV.B.3.p.(4) Mitigation Measures and Recommendations for Additional Investigation	IV-157
IV.B.3.q.	Energy	IV-157
	IV.B.3.q.(1) Existing Conditions	IV-157
	IV.B.3.q.(2) Impacts	IV-158
	IV.B.3.q.(3) Mitigation	IV-159
IV.B.3.r.	Visual Impacts	IV-160
	IV.B.3.r.(1) Introduction	IV-160
	IV.B.3.r.(2) Methodology	IV-160

IV.B.3.r.(3).	Existing Visual Environment	IV-161
IV.B.3.r.(4).	Visibility Analysis	IV-162
IV.B.3.r.(5).	Visual Impact Assessment	IV-162
IV.B.3.r.(6).	Visual Impact Mitigation	IV-164
IV.B.3.s.	Regional and Local Land Use Plans	IV-165
IV.B.3.s.(1).	No Build Alternative	IV-165
IV.B.3.s.(2).	Build Alternative	IV-166
IV.B.3.t.	Parks and Recreational Facilities	IV-167
IV.B.3.u.	Construction Impacts	IV-167
IV.B.4	Relationship Between Short-Term Uses of Man's Environment and the Maintenance and Enhancement of Long-Term Productivity	IV-168
IV.B.5.	Any Irreversible or Irrecoverable Commitments of Resources That Would Be Involved in the Proposed Action	IV-169
IV.B.5.a.	No Build Alternative	IV-169
IV.B.5.b.	Relocation Alternative	IV-169
IV.B.6.	Adverse Environmental Impacts that Cannot be Avoided or Adequately Mitigated	IV-170
IV.B.6.a.	No Build Alternative	IV-170
IV.B.6.b.	Relocation Alternative	IV-170
IV.B.7.	Indirect/Secondary & Cumulative Impacts	IV-171
IV.B.7.a.	Indirect or Secondary Impacts	IV-171
IV.B.7.b.	Cumulative Impacts	IV-171

**CHAPTER V - EVALUATION AND COMPARISON OF ALTERNATIVES** V-1

V.A.	Cost/Benefit Comparison	V-1
V.A.1.	Fulfillment of Project Objectives	V-1
V.A.1.a.	No-Build	V-1
V.A.1.b.	Relocation Alternative	V-1
V.A.2.	Monetary Cost and Economic Benefits	V-1
V.A.2.a.	No-Build	V-1
V.A.2.b.	Relocation Alternative	V-1
V.A.3.	Quantitative Benefits	V-3
V.A.3.a.	No-Build	V-3
V.A.3.b.	Relocation Alternative	V-3
V.A.4.	Qualitative Benefits	V-4
V.A.4.a.	No-Build	V-4
V.A.4.b.	Relocation Alternative	V-4
V.B.	Social, Economic, and Environmental Impacts	V-4
V.B.1.	No-Build	V-4
V.B.2.	Relocation Alternative	V-4
V.C.	Discussion and Recommendation	V-6
V.C.1.	No-Build	V-6
V.C.2.	Relocation Alternative – Recommended Alternative	V-9
V.C.2.a.	Recommended Site	V-9
V.C.2.b.	Staged Construction	V-9

**CHAPTER VI - DRAFT SECTION 4(f) EVALUATION (Not Applicable)** VI-1

**CHAPTER VII - PROJECT COORDINATION** VII-1

VII.A.	Introduction	VII-1
VII.B.	Pre-Scoping Public Participation	VII-1
VII.B.1.	Stakeholder Interviews	VII-1
VII.B.2.	Open House	VII-1

VII.C.	Scoping Process	VII-2
VII.D.	Project Newsletters and Website	VII-3
VII.E.	Project Information Meetings	VII-3
VII.F.	Agency Coordination	VII-4
	VII.F.1. Meeting on Traffic Issues	VII-4
	VII.F.2. Meetings on Siting	VII-8
	VII.F.3. Agency Consultation	VII-9
VII.G	Public Hearings to be Scheduled Following NYSTA and FHWA Approval of DEIS	VII-10

**CHAPTER VIII - LIST OF PREPARERS** VIII-1

**CHAPTER IX- LIST OF AGENCIES, ORGANIZATIONS, AND PERSONS TO WHOM COPIES OF THE STATEMENT ARE SENT** IX-1

**REFERENCES**

**INDEX**

**ABBREVIATIONS**

**APPENDICES**

**VOLUME II:**

Appendix A	Traffic Impact Study (Revised November 2005)
Appendix B	Toll Barrier Capacity Analysis (Revised November 2005)
Appendix C	Toll Barrier Development (Revised November 2005)
Appendix D	Siting Study (Revised November 2005)

**VOLUME III:**

Appendix E	Relocation Alternative Plans (Revised May 2006)
------------	---

**VOLUME IV:**

Appendix F	Economic Analysis (Revised November 2005)
Appendix G	Noise Analysis-Limit (Revised February 2006)
Appendix H	Air Quality Analysis (Revised May 2006)

**VOLUME V:**

Appendix I	General Ecology and Threatened/Endangered Species (Revised February 2006)
Appendix J	Wetlands Delineation (Revised February 2006)
Appendix K	Surface Water and Groundwater Quality Assessment (Revised October 2005)
Appendix L	Floodplain Evaluation (Revised April 2003)

**VOLUME VI:**

	Preface to the Cultural Resources Studies (Revised May 2006)
Appendix M-1	Phase IA Cultural Resources Assessment (Revised April 2002)
Appendix M-2	Phase IB Cultural Resources Investigation (Revised January 2002)
Appendix M-3	Supplemental Phase 1A & 1B Cultural Resources Evaluation (Revised February 2006)
Appendix M-4	Evaluation of Above-Ground Cultural Resources (Revised January 2006)

**VOLUME VII:**

Appendix N	Hazardous Waste/Contaminated Materials Assessment (Revised September 2005)
Appendix O	Asbestos Assessment (Revised February 2006)
Appendix P	Farmland Protection Assessment (Revised September 2005)

Appendix Q Visual Impact Assessment (Revised January 2006)  
Appendix R Land Use Assessment (Revised February 2006)

## FIGURES

- II-1 Project Location Map
- II-2 Project Study Corridor
- II-3 Population Density
- II-4 Elevation of Existing Williamsville Toll Barrier Looking West
- II-5 Existing Toll Barrier Plan
- II-6 Typical Existing Pavement Section
- II-7 Interchange 49 Toll Plaza Looking West
  
- III-1 Typical Toll Barrier Elements
- III-2 Interior Plaza Configuration
- III-3 Exterior Plaza Configuration
- III-4 Split Plaza Configuration
- III-5 Relocation Alternative Preferred Plaza Configuration-Tunnel Access to Toll Booths
- III-6 Relocation Alternative Preferred Plaza Configuration-Overhead Access to Toll Booths
- III-7 Primary Improvement Scenario
- III-8 Typical Configuration of Moderate Speed E-ZPass Lanes
- III-9 Secondary Improvement Scenario
- III-10 Hybrid Alternative—Scenario ES-1
- III-11 Hybrid Alternative—Scenario ES-2
- III-12 Hybrid Alternative—Scenario ES-2A
- III-13 Relocation Alternative Study Corridor
- III-14 MP 410 - Concept Plan
- III-15 MP 408-409 - Concept Plan
- III-16 MP 404-405 – Concept Plan
- III-17 Projected Traffic Impacts on the Network—Map 1
- III-18 Projected Traffic Impacts on the Network—Map 2
  
- IV-1 Bypass Corridors
- IV-2 Study Area Land Use & Bypass Corridors
- IV-3 Established Business Districts and Activity Centers
- IV-4 Existing Land Use
- IV-5 Noise Receptor Locations, Existing Toll Barrier, Williamsville
- IV-6 Noise Receptor Locations, Relocation Alternative Milepost 410
- IV-7 Noise Receptor Locations, Relocation Alternative Milepost 408-409
- IV-8 Noise Receptor Locations, Relocation Alternative Milepost 404-405
- IV-9 Maximum CO Levels at Modeled Receptors-Milepost 410
- IV-10 Maximum CO Levels at Modeled Receptors-Milepost 408-409
- IV-11 Maximum CO Levels at Modeled Receptors-Milepost 404-405
- IV-12 Wetland Locations, Relocation Alternative, Milepost 410
- IV-13 Wetland Locations, Relocation Alternative, Milepost 410
- IV-14 Wetland Locations, Relocation Alternative, Milepost 408-409
- IV-15 Wetland Locations, Relocation Alternative, Milepost 408-409
- IV-16 Wetland Locations, Relocation Alternative, Milepost 404-405
- IV-17 Wetland Locations, Relocation Alternative, Milepost 404-405
- IV-18 Primary and Sub-Drainage Basins, Relocation Alternative, Milepost 410
- IV-19 Primary and Sub-Drainage Basins, Relocation Alternative, Milepost 408-409
- IV-20 Primary and Sub-Drainage Basins, Relocation Alternative, Milepost 404-405
- IV-21 Floodplains within Relocation Alternative, Milepost 404-405
- IV-22 Farmland and Agricultural Districts Impacted by Relocation Alternative, Milepost 410
- IV-23 Farmland and Agricultural Districts Impacted by Relocation Alternative, Milepost 408-409
- IV-24 Farmland and Agricultural Districts Impacted by Relocation Alternative, Milepost 404-405

V-1 Comparison of Impacts

**TABLES**

II-1	Summary of Encroachments
II-2	Existing Interstate Traffic Volumes Year 2001
II-3	No-Build, Future Interstate 90 Traffic Volumes Year 2008 and 2028
II-4	Existing Interstate 90 Highway Segments LOS & Density, Year 2001
II-5	No-Build Future Interstate 90 Highway Segments LOS & Density, Years 2008, 2028
II-6	Design Hour Estimated Delay at Toll Barrier and Plazas (Year 2001)
II-7	No-Build Delay Estimate at Williamsville Toll Barrier
II-8	Accident Rates
II-9	Summary of Accident Locations and Probable Causes for the Williamsville Toll Barrier in 2000
II-10	Existing Bridges
II-11	Existing Utilities Along Project Corridor
II-12	Existing Utilities at Toll Barrier
III-1	Critical Toll Barrier Design Elements
III-2a	Design Criteria-Interstate 90 from Interchange 50 to Interchange 49
III-2b	Design Criteria-Interstate 90 from Interchange 49 to Interchange 48A
III-2c	Design Criteria-Interstate Highway Ramps
III-2d	Design Criteria-Rural Collectors Crossing over Interstate 90
III-3	Comparison of Critical Highway Parameters with Design Goals for Primary Improvement Scenario
III-4	Comparison of Critical Highway Parameters with Design Goals for Secondary Improvement Scenario
III-5	Comparison of Critical Highway Parameters with Design Goals for Hybrid Scenario ES-1
III-6	Comparison of Critical Highway Parameters with Design Goals for Hybrid Scenario ES-2
III-7	Comparison of Critical Highway Parameters with Design Goals for Hybrid Scenario ES-2A
III-8	Engineering Siting Scores
III-9	Social and Environmental Siting Scores
III-10	Combined Siting Score and Rank
III-11	Engineering Scores for ES-2A
III-12	Environmental Scores for ES-2A
III-13	Comparison of ES-2A Scores to Selected Relocation Sites
III-14	Traffic Flows at and in the Vicinity of the Williamsville Toll Barrier
III-15	Annual Vehicle Mix Origins/Destinations Between Interchange 49 and Interchange 50
III-16	Relocation Alternative, Roadway Segment Traffic Volumes
III-17	Design Hour Estimated Delay at Relocated Toll Barrier at the ETC (Year 2008) and Design Year (2028)
III-18	Design Hour Estimated Queues and Delays at Interchange 49 under the Relocation Alternative
III-19	Level of Service and Density Comparison for Critical Thruway and Local Roadway Segments
III-20	Level of Service and Delay Comparison for Critical Intersections
III-21	Bridge Traffic Design Values
III-22	Existing Utilities in Proximity to Leading Sites of the Relocation Alternative
III-23	ROW Acquisition-Milepost 410
III-24	ROW Acquisition-Milepost 408-409
III-25	ROW Acquisition-Milepost 404-405
III-26	Recommended Light Trespass/Spill Limitations

---

III-27	Relocation Alternative Costs Full Build-out with Overhead Access (2008 Dollars)
IV-1	Population Estimates for Municipalities Affected by the No-Build and Build/Improvement Alternatives
IV-2	Regional Economic Data
IV-3	Median Household Income-2000 US Census
IV-4	1990 and Projected 2025 Employment Primary Bypass Corridors
IV-5	Regional Construction Phase Economic Impacts
IV-6	Noise Levels of Common Sources
IV-7	Noise Abatement Criteria
IV-8	Existing Noise Levels at Receptors
IV-9	Noise Modeling Results-Existing Barrier
IV-10	Noise Modeling Results-Milepost 410
IV-11	Noise Modeling Results-Milepost 408-409
IV-12	Noise Modeling Results-Milepost 404-405
IV-13	Noise Abatement Evaluation
IV-14	Not Used
IV-15	MP410 CO Modeling Results for the Critical Emission Year (2008)
IV-16	MP408-409 CO Modeling Results for the Critical Emission Year (2008)
IV-17	MP404-405 CO Modeling Results for the Critical Emission Year (2008)
IV-18	Relocation Sites-PM <sub>10</sub> Modeling Results for the Critical Emission Year 2008
IV-19	Relocation Sites-PM <sub>2.5</sub> Modeling Results for the Critical Emission Year 2008
IV-20	Existing Toll Barrier-CO Modeling Results for the Critical Emission Year 2008
IV-21	Existing Toll Barrier-PM <sub>10</sub> Modeling results for the Critical Emission Year 2008
IV-22	Existing Toll Barrier-PM <sub>2.5</sub> Modeling Results for the Critical Emission Year 2008
IV-23	Emissions Summary for Mesoscale Analysis
IV-24	Not Used
IV-25	Impacts on Farmland Soils in Erie and Genesee Counties Protected under the Federal Farmland Protection Policy Act – Relocation Alternatives.
IV-26	Impacts on Agricultural District Lands at the Relocation Alternatives
IV-27	AD-1006 Farmland Impact Scores
IV-28	Annual Direct Energy Consumption
V-1	Project Objectives, Costs, and Economic Benefits
V-2	Quantitative and Qualitative Benefits
V-3	Comparison of Relocation Alternative Sites